

Addendum #2
Posted 1/18/2022

City of Kingman
Park Improvements

To All Bidders:

Identified below are clarifications and additions to the original RFB and are hereby made part of the bid documents as fully and completely as if the same were fully set forth therein. You must acknowledge this addendum on the bid form; failure to acknowledge may result in the rejection of your bid.

1. **Water and Sewer Main Taps:** The contractor should get the sewer line to the main and the City will install the tap. The City will tap the water main and get the service line to the meter can. The contractor will need to work with the City on the best placement for the meter can.
2. **Backflow Preventer:** The intent was to have one backflow preventer, sized to handle all the plumbing on site (irrigation system, splashpad, and restroom). If this is not a cost-effective solution given the maximum flow rate on the project site, an additional preventer should be proposed.
3. **Roof Panels for Restroom:** It has been brought to our attention that that roof panels in the plans for the restroom building are quite expensive and on order delays. As a result, contractors should feel free to consider an OR EQUAL substitute such as Metal Sales Image II 24 ga. Panels.
4. **Park Signs:** For the park signs, the plans call for the *frame* around the sign panel to be powder coated, but the sign panel itself to be a baked enamel finish on .080 aluminum, or equal. Also, from a design perspective, we do not want the font to look stenciled. Most sign companies should be able to produce this sort of a sign panel.